




Practicing Engineering Series

Geotechnical Instrumentation and Testing in Myanmar

18 May 2024, FMES-MSCE Knowledge Sharing Seminar



Win Naing Htun, B.E.(Civil), M.Eng.AIT, PE-0036(Structural), PE-0124(Geotechnical)
Visiting Associate Professor, Civil Engineering Department, YTU
Managing Director, Civil Solution Consultants Ltd. (CSC), Yangon, Myanmar
E-mail: csc1999@gmail.com, Web: <https://www.csc1999.com>

What is Instrument?




- It is a kind of measuring device
- It is a combination of physical/mechanical and electrical/electronic parts.
- It connects to Data Logger or Monitoring Device and Computer. It can be small, medium, large scale.
- It can be one time application or reusable.
- Some of them are:
(1) Tiltmeter (2) Piezometer (3) Inclinator (4) Strain Gauge (5) Pressure Transducer (6) Load Cell (7) Linear Variation Displacement Transducer, LVDT, etc.

TESTING



- **Scope of Work:** instrument + monitoring unit for tilting, leveling, inclination, settlement, loading, etc. for various engineering requirements such as building tilting, settlement, lateral movement, Pile Integrity, Pile Capacity (static and dynamic), etc.
- **Duty:** Public Safety
- **Responsibility:** Implementation in difficult situation, application in Permit to Work System.
- **Skills:** Task Risk Assessment, Field Oriented, Practicing in HSE Policy, Working at Height.
- **Ultimate Goal:** Safe and Durable working environment.

Figure 1: Instrumentation Plan



MEMS Digital Tiltmeter

Applications

The Model 6101D MEMS Digital Tiltmeter is designed to measure tilt in structures including...

- Buildings
- Dams
- Embankments
- Slopes
- Excavation walls
- Open pits



• Model 6101D MEMS Digital Tiltmeter shown with Model 6201-1C Ceramic Tiltplate.



• Model PPC-2 Field PC showing a Live Tiltmeter Data reading screen shot.



• Model 6201-1C Ceramic, 6201-1A Anodized Aluminum and 6201-1S Stainless Steel Tiltplates (tiltplates are permanently attached to structure being monitored).

Tilt Plate Installation Photo



Figure 5: Tiltmeter Monitoring Photos




Tilt Plate Monitoring Record (Tilt Plate - 02) (Zealax Hotel)




Location : Ahlone
 Installed On: 15/08/23
 Initial Reading On: 18/08/23
 Last Reading On: 25/10/23

Project: 1B + 6S RCC Building
 Consultant : SDG Group
 Client : SunShine Survey
 Limit: 0.78 °

Date & Time	Reading		Face Difference	Tilt	Cummulative Tilt in Degree °	Cummulative Tilt in Minute '	Cummulative Tilt in Second ''	Remark
	A+	A-						
18/08/2023 15:05:18	-122	65	-187	-0.1071	0.0000	0.0000	0.00	Initial Reading
23/08/2023 15:12:02	-110	76	-186	-0.1066	0.0006	0.0344	2.06	Sheet Piling Initiated
30/08/2023 10:58:13	-111	78	-189	-0.1083	-0.0011	-0.0688	-4.13	
06/09/2023 12:12:44	-98	42	-140	-0.0802	0.0269	1.6157	96.94	
13/09/2023 12:09:44	-129	69	-198	-0.1134	-0.0063	-0.3782	-22.69	Sheet Piling Finished
20/09/2023 12:09:44	-119	70	-189	-0.1083	-0.0011	-0.0688	-4.13	
27/09/2023 12:09:44	-141	73	-214	-0.1226	-0.0155	-0.9282	-55.69	
05/10/2023 11:11:37	-126	86	-212	-0.1215	-0.0143	-0.8594	-51.57	Before Excavation
11/10/2023 11:11:37	-116	83	-199	-0.1140	-0.0069	-0.4125	-24.75	Excavation Initiated
19/10/2023 14:30:50	-124	80	-204	-0.1169	-0.0097	-0.5844	-35.07	During Back Filling
25/10/2023 11:23:13	-123	69	-192	-0.1100	-0.0029	-0.1719	-10.31	Backng Filling Completed
02/11/2023 11:39:34	-124	74	-198	-0.1134	-0.0063	-0.3782	-22.69	Piling Initiated



**Tilt Plate Chronological Record in Vertical Plane
 (1-3 Plane, Vertical Direction)**





CIVIL SOLUTION CONSULTANTS LTD.
 Operation Off: No.413-414, Aung Thitsar St., 48 Ward, North Dagon
 Township, Yangon, Myanmar, 11421.
 Tel.: +95-9-5003281, +95-9-5077153, +95-9-798476843
 E-mail: info@csc1999.com; Web: www.csc1999.com



9001:2015 Certified

MEMS PORTABLE TILT METER TEST REPORT

Type : MEMS TILT METER
 Model Number : Geokon 6101-D
 Serial Number : 1820838
 Max: Capacity : 0 ~ 15°
 Ambient Temp : 27.5 Deg C

Calibration No : CSC- 54-23-Tilt-Meter-1820838
 Calibration Date : 21-Aug-23
 Technician : Aung Htet
 Checked By : Daw Yi Yi Khin
 Recommended Next Calibration: 20-08-2024



This calibration has been carried out by using Digital Total Station calibrated by Geo Applied International, Model: CTS-632R6, SN: 242974, Dated: 12-07-2023.

Applied Tilt (°Degree)	*** Reading from Tilt-Meter A-Axis (Digits) ***			Change	Linearity (% Max: Load)
	Cycle 1	Cycle 2	Avg:		
0.00000	70	70	70	0	
0.01667	82	81	82	12	0.39
0.03333	94	93	94	12	1.23
0.05000	105	106	106	12	2.07
0.06667	115	116	116	10	1.10
0.08333	125	126	126	10	0.13
0.10000	136	134	135	10	1.28
0.11667	148	145	147	12	0.90
0.13333	160	157	159	12	0.06
0.15000	171	172	172	13	1.69
0.16667	182	182	182	11	1.17

Gauge Factor : **0.0015** Degree/Digit

Calculated Tilt (°Degree) = G * (R₁ - R₀)

* Note : The above calibration uses a linear regression method. The Zero Reading shown is ideal for straight line computation and does not usually agree with the actual no-load reading.

** Linearity = ((Calculated Tilt - Applied Tilt) / Max. Applied Tilt) x 100%




Figure 6: Casagrande Piezometer & Water Level Monitoring



Solinst

Coaxial Cable Water Level Meter

[More Info](#) | [Instructions](#) | [Get Quote](#)

[Model 102 Data Sheet](#)



Water Stand Pipe (Water Level Monitoring Record)




Location : Ahlone
 Installed On: 15,16,17,18-08-2023
 Initial Reading On: 18/08/23
 Last Reading On: 12/10/23

Project: 1B + 6S RCC Building
 Consultant : SDG Group
 Client : SunShine Survey

Date & Time	Water Level Reading (mm) (From BH Top)				Water Level Difference frm Initial Reading (mm)				Remark
	WP(1) Zelax Hotel	WP(2) Near Building	WP(3) RiverSide	WP(4) Road Side	WP(1)	WP(2)	WP(3)	WP(4)	
18/08/23	4,400	2,300	6,100	4,000	0	0	0	0	Initial Reading WP(2) flooded due to close Sheet Piling. WP(4) flooded due to possible pipe leak.
23/08/23	5,000	7,800	5,000	6,500	600	5,500	-1,100	2,500	
30/08/23	1,050		4,200	6,500	-3,350		-1,900	2,500	
06/09/23	8,700		8,300		4,300		2,200		
13/09/23	7,200		1,250		2,800		-4,850		
20/09/23	6,170		8,650		1,770		2,550		
27/09/23	5,500		5,900		1,100		-200		
05/10/23	7,000		5,100		2,600		-1,000		
12/10/23	4,850		4,700		450		-1,400		

Water Level Difference (mm) (From BH Top)



Inclinometer Casing Installation & Drilling Rig



Figure A2: Inclinometer Casing Specification



CEP



Digital Inclinometer System

Applications

The Model GK-604D Digital Inclinometer System is used to determine and measure the lateral movements in and around...

- Landslides
- Unstable Slopes
- Dam Embankments
- Landfills
- Slurry walls
- Caissons
- Piles
- Sheet Piling
- Tunnels



Model GK-604D Digital Inclinometer System.

System Components



Model 6100D Digital Inclinometer Probe.

Figure 4: Inclinometer Monitoring Photos



Inclinometer Monitoring Record (Inclinometer - 01)

Location : Ahlone
 Installed On: 15/08/23
 Initial Reading On: 19/08/23
 Last Reading On: 25/10/23

Project: IB + 6S RCC Building
 Consultant : SDG Group
 Client : SunShine Survey
 Hole Depth : 12m (Only 9m Readable)

N : 1857989.510
 E : 193577.814
 Z : 5.179

A-axis Max Movement : 0 ~ 5 mm
 B-axis Max Movement : 0 ~ 5 mm

Remark: *(Sheet Piling Works completed)
 (Excavation Works completed & Backfilling On Going)
 (Data From Initial(After Sheet Piling), Before Excavation, After Excavation are displayed)*





CIVIL SOLUTION CONSULTANTS LTD.
 Operation Off: No.413-414,Aung Thisar St., 48 Ward, North Dagon Township, Yangon, Myanmar, 11421.
 Tel.: +95-9-5003281, +95-9-5077153, +95-9-798476843
 E-mail: info@csc1999.com; Web: www.csc1999.com





MEMS INCLINOMETER TEST REPORT

Type : MEMS INCLINOMETER Calibration No : CSC- 55-23-Inclinometer-110673
 Model Number : Geokon 6100-D Calibration Date : 21-Aug-23
 Serial Number : 1306731 Technician : Aung Htet
 Max. Capacity : 0 ~ 30° Checked By : Daw Yi Yi Khin
 Ambient Temp : 27.9 Deg C Recommended Next Calibration: 20-08-2024

This calibration has been carried out by using Calibrated LVDT, Model: SDP C100, SN: BAB141539, traceable to Cert No: CSC-SI-23-LVDT-BAB141539, Dated: 02-07-2023.





Applied Inclinometer Casing Movement (mm)	*** Reading from Inclinometer A-Axis (Digits) ***			Change	Linearity (% Max. Load)
	Cycle 1	Cycle 2	Avg.		
0.00	-58	-60	-59	0	
5.30	33	35	34	93	0.19
10.00	118	120	119	85	0.03
15.46	204	206	205	86	1.32
20.86	289	290	290	85	2.62
25.80	373	377	375	86	2.90
30.50	463	468	465	90	2.15
35.50	551	560	556	90	2.01
40.16	635	640	637	82	2.15
44.08	725	735	730	93	0.45
49.08	815	830	823	93	0.87


Gauge Factor : **0.0562** mm/Digit

Calculated Displacement (mm) = G * (R₁ - R₀)

* Note : The above calibration uses a linear regression method. The Zero Reading shown is ideal for straight line computation and does not usually agree with the actual no reading.

** Linearity = ((Calculated Displacement - Applied Displacement) / Max. Applied Displacement) x 100%






PILING LAYOUT PLAN




REFERENCE BORE HOLE (ZONE C1)	SIZE OF BORED PILE	WORKING LOAD PER PILE	ESTIMATED PILE PENETRATION FROM PILE CUT-OFF LEVEL (-1.20m FROM GROUND FLOOR LEVEL)	NO. OF PILE
BH 17,18,19,20	800#	380t	46.5 M	121
			TOTAL NO. OF PILE	121

NOTE: LIFT PILECAP CUT-OFF LEVEL (-2.9m FROM GROUND FLOOR LEVEL) TO BE VERIFIED WITH M&E

Figure 2: Instrumentation Detail for 800mm Dia: Bored Pile (ULT-Test Only)



Longitudinal Cross Section
(Scale = None)



Concrete Embedment Strain Gages

Vibrating Wire Readout

Applications

The Model 4200, 4202 and 4210 are designed to measure strains in or on...

- Foundations
- Piles
- Bridges
- Dams
- Containment vessels
- Tunnel liners
- Mass concrete with coarse aggregates
- Laboratories and/or where space limitations exist (Model 4202)



● Model 4202 (front), Model 4200 (center) and Model 4210 (rear) Concrete Embedment Strain Gages.



Figure 1: Model 4200 and 4200L Vibrating Wire Strain Gage

Figure 5: Attaching Model 4200 Strain Gages to ULT Pile Rebar Cage



2 VWSGs Layer (Middle Layers)




Figure 6: Attaching Cables Rebar Cage



7: Rebar Cage Lowering to BH & Lapping Area



Figure 9: Water Resistant DT Connectors




Figure 8: Last Cage & Sensors Checking after Concreting





Static Load Test for Bored Pile, City Loft West

Figure F1: ULT Test Inverted Beam System Setup





PWH-PA High capacity Pressure Transducer 70~200MPa




The PWH-PA high-capacity pressure transducer has a sealed structure made with high-strength stainless steel. Using this highly sensitive transducer, stable high-accuracy measurement can be made over a long period of time. It is used to control plant or production lines, to measure jack pressure, and for various other applications. Protection ratings: IP65 equivalent.

■ SPECIFICATIONS

	PWH-70MPa	PWH-100MPa	PWH-150MPa	PWH-200MPa
Capacity	70MPa	100MPa	150MPa	200MPa
Rated Output		1mV/20000 10 ⁶ strain ±1%		
Exciters	0.2%RO			
Excitance	0.2%RO			
Repeatability	0.2%RO			
Temperature effect zero	0.02%/°C			
Temperature effect span	0.02%/°C			
Compensated temperature range	-10 ~ +60 °C			
Allowable temperature range	-25 ~ +70 °C			
Clearance	150%			
Ultimate overloading	300%			
Input/Output resistance	200±1%			

High capacity Available for many fields of industrial application such as plant, production line, jack pressure, etc.

Load Cells




CEP 2000 KN Ground Anchor Load Cell

CEP 10,000 KN Load Cell

DISPLACEMENT TRANSDUCERS

SDP-C Displacement Transducer 50/100mm



The SDP-C displacement transducer is a general-purpose, strain gauge type transducer. Designed with a strain-generating cantilever, it is able to make stable measurement while maintaining the high sensitivity to minuscule displacements.

Protection ratings: IP40 equivalent.

■ Dimensions

TYPE	A	B	C	D
SDP-50C	130	70	50	80
SDP-100C	220	120	80	130

■ SPECIFICATIONS

TYPE	SDP-50C	SDP-100C
Capacity	50mm	100mm
Rated Output	2.5mV/(5000x10 ⁶ strain) ±0.2%	
Sensitivity to Temperature	100	50
Non-linearity	0.2%RO	
Spring force	5.0N	
Frequency response	1Hz	
Allowable temperature range	0 ~ +60°C (no condensation)	
Input/Output resistance	350Ω	
Recommended operating voltage	2V or less	
Allowable exciting voltage	5V	
Weight	250g	350g

Supplied cable: CTE-VT10NLS-TB (φ5mm 0.3mm² 4-core shielded vinyl cable 10m)

CR1000 Measurement and Control Datalogger

The CR1000 provides precision measurement capabilities in a rugged, battery-operated package. It consists of a measurement and control module and a wiring panel. Standard operating range is -25° to +50°C; an optional extended range of -55° to +85°C is available.






Figure 3: Test Pile Preparations



Figure F4: Level Checking





LINEAR VARIATION DISPLACEMENT TRANSDUCER CALIBRATION



Type : LVDT Calibration No : CSC-46-23-LVDT-BAB141544
 Model Number : SDP-C100 Calibration Date : 03-July-2023
 Serial Number : BAB141544 Ambient Temp : 35.49 Deg C
 Max. Range : 0 ~ 100 mm Technician : Thant Zin Zaw
 Cable Length : 0.5 m Checked By : Daw Yi Yi Khin




This calibration has been carried out by using Glass Plates, calibrated by Department of Research & Innovation, Cert No: DRI/NSOD/23/J-0113-0125 Dated: 23-03-2023.

Applied Glass Plates (mm)	*** Reading from CR-800/1000 Datalogger (or) Reading from TC32K (µε) ***			Change	Linearity (% Max: Displacement)
	Cycle 1 (up)	Cycle 2 (down)	Avg:		
0.00	0	0	0.00	0	
10.00	-507	-505	-506.00	-506	0.02
20.00	-1011	-1006	-1008.50	-503	-0.03
30.00	-1514	-1506	-1510.00	-502	-0.10
40.00	-2019	-2009	-2014.00	-504	-0.12
50.00	-2527	-2516	-2521.50	-508	-0.07
60.00	-3028	-3021	-3024.50	-503	-0.11
70.00	-3537	-3528	-3532.50	-508	-0.06
80.00	-4040	-4035	-4037.50	-505	-0.06
90.00	-4545	-4538	-4541.50	-504	-0.08
100.00	-5044	-5044	-5044.00	-503	-0.13

Gauge Factor : **-0.0198** mm/µε Regression Zero Reading: **0.02**

Calculated Displacement (mm) = G * (R₁ - R₀)

* Note : The above calibration uses a linear regression method. The Zero Reading shown is ideal for straight line computation and does not usually agree with the actual no-load reading.
 ** Linearity = ((Calculated Disp: - Applied Disp:) / Max. Applied Disp:) x 100%



LVDT
CSC-46-23-BAB141544
BAB141544
0 - 100 mm
03-July-2023
03-July-2024
-0.0198 mm/µε



PRESSURE TRANSDUCER CALIBRATION REPORT



Type : Pressure Transducer Calibration No : CSC-65-23-TML-PT-CHT211012
 Brand : TML Calibration Date : 09/Sep/2023
 PG SN : CHT211012 Technician : Aung Htet
 Max. Range : 0 ~ 70 MPa Checked By : Daw Yi Yi Khin
 Ambient Temp : 33.21 Deg C Next Calibration : 08/Sep/2024




This calibration has been carried out by using referenced Pressure Gauge Calibrated By Department of Research & Innovation, Serial No: 1104972768, traceable to Cert No: P-030-23 Dated: 23-03-2023.

Referenced Gauge Reading (Bar)	*** Reading from Pressure Transducer / TC-32K Readout (µε) ***			Change	Linearity
	Cycle 1	Cycle 2	Avg:		
0	-32	-32	-32		
600	88	87	88	119.5	0.08
1200	205	205	205	117.5	0.06
1800	320	322	321	116.0	-0.06
2400	439	440	440	118.5	-0.03
3000	559	561	560	120.5	0.11
3600	679	681	680	120.0	0.22
4200	794	797	796	115.5	0.08
4800	918	921	920	124.0	0.42
5400	1032	1035	1034	114.0	0.19
6000	1144	1147	1146	112.0	-0.14
6600	1268	1269	1269	123.0	0.14
7200	1385	1384	1385	116.0	0.02
7800	1501	1501	1501	116.7	-0.05
8400	1620	1622	1621	119.8	0.05
9000	1738	1740	1739	118.0	0.05

Gauge Factor : **5.0845** psi/µε Regression Zero Reading: **156.27**

Calculated Pressure (psi) = G * (R₁ - R₀)

* Note : The above calibration uses a linear regression method. The Zero Reading shown is ideal for straight line computation and does not usually agree with the actual no-load reading.
 ** Linearity = ((Calculated Pressure - Applied Pressure) / Max. Applied Pressure) x 100%





CIVIL SOLUTION CONSULTANTS LTD.
 Operation Off: No.413-414, Aung Thitsar St., 48 Ward, North Dagon
 Township, Yangon, Myanmar, 11421
 Tel.: +95-9-5003281, +95-9-5077153, +95-9-798476843



LOAD CELL GAUGE FACTOR DETERMINATION



Type : Resistance Wire Load Cell
 Calibration No : CSC-63-23-CEP-2521-RWL
 Mode Number : CEP
 Calibration Date : 07/09/2023
 Serial Number : 2521
 Ambient Temp : 34.0 Deg C
 Max: Capacity : 0 ~ 1000 Tons
 Technician : AH
 Jack Eff. Area : 227.19 in2
 Checked By : Daw Yi Yi Khin
 PG SN : 1106164807
 Recommended Next Calibration : 06/09/2024



This calibration has been carried out by using **Pressure Gauge** calibrated by DRI, Serial No: 1106164807, Certificate No: **P-065-23/26-06-2023**.


Applied Pressure (PSI)	Applied Loading (Ton)	*** Reading from CR-800/1000 Datalogger (or) TC-32K Readout (µs) ***			Change	Linearity (% Max: Load)
		Cycle 1	Cycle 2	Avg:		
0.00	0	1137	1137	1137	0	
1,000	101	1830	1830	1830	693	0.53
2,000	203	2489	2489	2489	659	0.31
3,000	304	3151	3151	3151	662	0.26
4,000	406	3816	3816	3816	665	0.15
5,000	507	4488	4495	4492	676	0.36
6,000	609	5156	5130	5143	651	-0.01
7,000	710	5824	5818	5821	678	0.24
8,000	811	6492	6486	6489	668	0.31
0.00	0	1138	1138	1138		

Gauge Factor : **0.1520** tons/µs Regression Zero Reading: **1138.00**

Calculated Load (Tons) = G * (R₁ - R₀)

* Note : The above calibration uses a linear regression method. The Zero Reading shown is ideal for straight line computation and does not usually agree with the actual no-load reading.

** Linearity = ((Calculated Load - Applied Load) / Max. Applied Load) x 100%



Load Cell Calibration



CIVIL SOLUTION CONSULTANTS LTD.
 Operation Off: No.413-414, Aung Thitsar St., 48 Ward, North Dagon
 Township, Yangon, Myanmar, 11421
 Tel.: +95-9-5003281, +95-9-5077153, +95-9-798476843



LOAD CELL GAUGE FACTOR DETERMINATION



Type : Resistance Wire Load Cell
 Calibration No : CSC-64-23-CEP-2522-RWL
 Mode Number : CEP
 Calibration Date : 07/09/2023
 Serial Number : 2522
 Ambient Temp : 34.7 Deg C
 Max: Capacity : 0 ~ 1000 Tons
 Technician : AH
 Jack Eff. Area : 227.19 in2
 Checked By : Daw Yi Yi Khin
 PG SN : 1106164807
 Recommended Next Calibration : 06/09/2024



This calibration has been carried out by using **Pressure Gauge** calibrated by DRI, Serial No: 1106164807, Certificate No: **P-065-23/26-06-2023**.


Applied Pressure (PSI)	Applied Loading (Ton)	*** Reading from CR-800/1000 Datalogger (or) TC-32K Readout (µs) ***			Change	Linearity (% Max: Load)
		Cycle 1	Cycle 2	Avg:		
0.00	0	666	666	666	0	
1,000	101	1329	1350	1340	674	0.21
2,000	203	2006	2004	2005	666	0.15
3,000	304	2670	2667	2669	664	0.17
4,000	406	3344	3336	3340	672	0.22
5,000	507	4010	3970	3990	650	-0.01
6,000	609	4680	4646	4663	673	0.07
7,000	710	5350	5307	5329	665	0.13
8,000	811	6019	5969	5994	665	0.19
0.00	0	666	668	667		

Gauge Factor : **0.1525** tons/µs Regression Zero Reading: **668.00**

Calculated Load (Tons) = G * (R₁ - R₀)

* Note : The above calibration uses a linear regression method. The Zero Reading shown is ideal for straight line computation and does not usually agree with the actual no-load reading.

** Linearity = ((Calculated Load - Applied Load) / Max. Applied Load) x 100%



Load Cell Calibration

2: Observed Applied Load vs Pile Top Settlement (Summary)




Figure A4: Pile Top Applied Load vs Time vs Top Settlement (Auto Logging)








Figure 1: Load Transfer Curve (Summary) with Sub Soil Data BH-17



Load Transfer Curve and Unit Skin Friction of 2nd Loading Cycle




Load Transfer Curve and Unit Skin Friction of 3rd Loading Cycle





**HPBC inspection; Static Pile Load Test for bored pile
ASTM D1143**



The Central Project



The Yoma Land Project



Static Load Test for Press Pile, Thilawa SEZ



ASTM D1143





STATIC PILE LOAD TEST WITH KENTLEDGE SYS
 Shangrila Kandawgyi Project



Verification Pile Test



Kanthayar Project

STATIC PILE LOAD TEST WITH INVERTED BEAM SYSTEM







Figure 5: Lateral or Horizontal Load Testing Schematic

DESIGNED BY:  09-44-19-1
 CIVIL SOLUTION CONSULTANTS LTD.
 NO. 413, 10-10 AVONUE, AUNG MYETHAZAR ST., 48
 NORTH DAGON MYOTHIT TOWNSHIP, YANGON
 TEL: +95-9-5077153, +95-9-5003281
 E-mail: csc1999@gmail.com, Web: www.csc1999.com



Myanmar Petroleum Products Storage and Distribution Terminal Thilawa Project Thanlyin, Myanmar (Horizontal Load Test Photographs)



System



Hydraulic Jacks, & LVDTs



Operating Electric Pump



Data Logger Panel





Figure 3: Compression Load Testing Schematic



Myanmar Petroleum Products and Distribution Terminal Thilawa Project, Thanlyin, Myanmar (Static Axial Compression Load Test Photographs)



Kentledge System




Hydraulic Jacks, Load Cells & LVDTs



Operating Electric Pump



Data Logger Panel



: PIT/SIT Testing Photo on Bored Pile / Spun Pile



PET Equipment

A synthetic pile and the reflectogram



ASTM D5882







Table 1: Typical reflectograms

PILE PROFILE	DESCRIPTION	REFLECTOGRAM
	Straight pile, free end, length as expected	
	Straight pile, fixed end, length as expected	
	Straight pile, free end, shorter than expected	
	Increased impedance	
	Decreased impedance	
	Locally increased impedance	
	Locally decreased impedance	
	Multiple reflections from mid-length discontinuity - toe reflection indiscernible	
	Irregular profile - irregular reflectogram	



Avg:24

Start Impact Data Info

Save Amp:2.00 A View Compare



PIT test at Mawlamyine Bridge



16 January 2024 2:43 pm



16 January 20



ASTM D 5882 – 07 Compliance Statement

I hereby confirm that the **PET** system, running **PET** Version 3.0.0 (or higher) meets, or exceed, the requirements of ASTM Standard D5882-07.

Date: 1/1/2008




Joram M. Amir
President
Piletest.com

A4: PET Equipment Calibration Report



Developing, manufacturing and marketing of deep foundations quality assurance NDT equipment since 1996

PET system S/N	25332 (3322)
Date	2022-07-12

Declaration of conformance TO ASTM D5882-16

I hereby confirm that the above PET system running PET Version 3.02 (or higher) complies with the requirements of ASTM Standard D5882-16

CERTIFICATE OF In-house CALIBRATION

Calibration Date	2022-07-12
Valid till:	2025-07-12

I hereby certify that the above PET sensor was successfully calibrated according to all the requirements of ASTM standard D5882-16 using the in-house method CALPT02.







ASTM D6760

SONIC LOGGING TEST (ULTRASONIC CROSS-HOLE)

P2-BP1
2/20/19
Diameter: 0.80m

Profile: 23	Profile: 24	Profile: 34
14.40m	14.45m	14.44m
Distance: 0.30m	Distance: 0.50m	Distance: 0.30m
Filter: 2	Filter: 2	Filter: 2



Sonic Logging Test

Figure 1





Figure 2





Testing




CHUM System



Shay Gyi Bridge Project, Yargyi-Kalaywa Road



Transducers



Results

PDA and DLT



ALLNAMICS PDR PILE TESTING SYSTEM for PDA and DLT

ALLNAMICS PDR PILE TESTING SYSTEM for PDA and DLT

Pile Driving Analysis (PDA) and Dynamic Load Testing (DLT)

The Hague Office
Waterpas 98
2495 AT The Hague
The Netherlands
Tel: +31703077499

Heemskerk Office
De Trompet 1585
1967 DB Heemskerk
The Netherlands
Tel: +31251245752

Tyler Office
1411 Cumberland Rd
Tyler, TX 75703
U.S.A.
Tel: +19032160038

Singapore Office
3 Joo Koon Crescent
639088 Singapore
Tel: +6597713615

info@allnamics.eu
www.allnamics.eu



*Combined acceleration strain transducers,
multipurpose template, for transducer mounting
and transport and transducers connectors with
protection caps.*



Features:

- WiFi or ethernet connection to a Windows PC laptop
- 4 channels (easy upgrade to 8 channel monitoring under development)
- Adjustable sample rate (up to 48 kHz per channel)
- 24 bit conversion
- Internal Solid State recorder for signal backup
- 6 hrs operational battery life (16 hrs standby)
- Class IP67 housing
- Robust design with easy magnetic stowaway system for excess cable
- Fully compatible with intelligent combined transducers (USID)
- Integrated test box (to automatically check the transducers during mounting)
- Software program for monitoring, processing and reporting included





Typical PDA Test ASTM D-4945 GeoLab Myanmar Co., Ltd.



Typical PDA Test ASTM D-4945 GeoLab Myanmar Co., Ltd.





DYNAMIC PILE LOAD TEST FOR PUSHED PILE






DYNAMIC PILE LOAD TEST FOR BORED PILE






Pile Dynamic Analysis

Dynamic Load Test




ALLNAMICS PDR PILE TESTING SYSTEM for PDA and DLT





Test Pile



PDA-DLT Equipment

PDA Monitoring Results: P3-No.5

Pile No. : P3-No.5
 Date of Testing : 13.8.2019
 Pile Penetration : 7.25 (m)
 Measured Length : 7.45 (m)
 Total Length : 8.00 (m)
 Transferred Energy : 12.4 (kJm)
 Stat: Resistance RMX : 1059.0 (kN)







Table 1. Summary of Pile Record

Pile No.	Date Driven	Total Length (m)	Measured Length (m)	Penetration (m)	Working Load(kN)
P3-No.5	25.7.2019	8.00	7.45	7.25	400
P1-No.5	31.7.2019	8.00	7.35	7.10	400
L1-No.5	30.7.2019	8.20	7.50	7.20	400
P1-No.3	31.7.2019	7.50	6.80	6.60	400

Table 2. Summary of Field Results

Pile No.	Date Tested	Field Static Resistance (kN)	Max. Comp: Stress (MPa)	Transferred Energy (kJNm)	Pile Integrity (BTA %)
P3-No.5	13.8.2019	1059.0	27.3	12.4	100%
P1-No.5	15.8.2019	700.1	21.4	18.5	100%
L1-No.5	13.8.2019	773.8	20.2	11.1	100%
P1-No.3	13.8.2019	629.8	18.7	11.7	100%

Table 3. Summary of Signal Matching Results

Pile No.	Skin Friction Mobilized(kN)	Toe Resistance Mobilized(kN)	Total Resistance (kN)	Pile Head Settlement@ WL (mm)	Pile Head Settlement@ 2WL (mm)
P3-No.5	487	563	1050	1.68	5.52
P1-No.5	209	563	772	3.16	8.73
L1-No.5	249	563	811	2.72	8.85
P1-No.3	230	442	672	3.15	7.61

CALIBRATION SHEET PDA-STRAIN SENSOR



Transducer information:

Serial number : **S019**
 Manufacturer : Allnamics Pile Testing Experts
 Calibration factor : **4.76** (mV/V, @ 2000 uE)
 Zero balance : **0.46** mV/V
 Calibration date : **30-04-2018**
 Calibrated by : MVE

1) The end user is responsible for a recalibration of the transducer.

Typical sensor specification:


Model : 4 Foil gages TLM FLA-2-350-23
 Manufacturer : TLM, Allnamics
 Range : +/- 1500 uE
 Zero : +/- 10 mV
 Excitation : 10 V
 Input impedance : 350 Ω
 Output impedance: 350 Ω

Max rating : +/- 4000 uE
 Non-linearity : 1 % FS
 Operating range : -20 to 60 °C

Calibration equip. : Traceable to Metric Control

Wiring and mounting:

Signal	Sensor	Cable	Connector
+V	Red	Red	A
+S	Blue	Green	B
-S	White	White	C
-V	Black	Blue	E
		Shield	F



Connector : MIL-C-26482, 10-06, male plug
 Cable : 4x AWG24/7, PUR, water blocking, Allnamics.
 SID : Sensor Identification
 Dimensions : 122x40x10 mm (lxbxh)
 IP class : 66
 Mounting : 2x DIN 912, M8
 Span : 65 mm

Allnamics Pile Testing Experts B.V.

Address : Waterpas 98
 2495 AT The Hague
 The Netherlands
 Web : www.allnamics.eu
 Tel. : +31 - 70 - 3077499

This certificate shall not be reproduced.



Figure 4: Tension or Uplift Load Testing Schematic





Figure G1: Compression Test & Lateral Test



G3: Tension Test



Figure A1: Test Pile Locations



No.	Pile No.	Pile Size		Pile Type		Pile Depth		Pile Location	
		Ø (mm)	L (m)	Ø (mm)	L (m)	Ø (mm)	L (m)	Ø (mm)	L (m)
1	F25-H01	300	12	300	12	12	12	12	12
2	F20-U01	300	12	300	12	12	12	12	12
3	F30-C03	300	12	300	12	12	12	12	12



**PILE COMPRESSION LOAD TESTS,
LATERAL LOAD TESTS & PULLOUT TESTS REPORT**
Minbu Solar Firm

Figure 2: F30-C03 (Compression Test 300% Result)




Figure 3: F25-H01 (Lateral Test 300% Result)





Figure 5: F20-U01 (Tension Test 300% Result)



Minbu Solar Farm Project, Phase 2, Magway Region

Proposed Loading Cycle For **Tension/Pull out Test** on **350mm Dia Pile**

1st Cycle Working Load =	13.7 kN	1.37 tonnes	
Times =	3.0		
2nd Cycle Test Load =	27.4 kN	2.74 tonnes	
3rd Cycle Test Load =	41.1 kN	4.11 tonnes	

Jack Model : **CSLRG**

QUICK LOAD TEST (QLT)

Shanxi Construction & Investment
Group (Myanmar) Co., Ltd.
(11/07/2022) Rev01




Minimum Loading times for pile test

Test Load as %WL	Min Holding	Recording	kN	Min (kN)	Max (kN)	kN	Min (tonne)	Max (tonne)	REMARKS
0%	-	-	0.00	0.0	0.0	0.00	0.0	0.0	
25%	4min	4min (2)	3.43	3.2	3.6	3.4	0.3	0.4	
50%	4min	4min (2)	6.85	6.6	7.2	6.9	0.7	0.7	
75%	4min	4min (2)	10.28	9.8	10.8	10.3	1.0	1.1	
100%	5min	(3)	13.70	13.0	14.4	13.7	1.3	1.4	
125%	4min	4min (2)	17.13	16.2	18.0	17.1	1.6	1.8	
150%	4min	4min (2)	20.55	19.6	21.6	20.6	2.0	2.2	
175%	4min	4min (2)	23.98	22.8	25.2	24.0	2.3	2.5	
200%	5min	(3)	27.40	26.0	28.8	27.4	2.6	2.9	
225%	4min	4min (2)	30.83	29.3	32.3	30.8	2.9	3.2	
250%	4min	4min (2)	34.25	32.6	36.0	34.3	3.3	3.6	
275%	4min	4min (2)	37.68	35.8	39.6	37.7	3.6	4.0	
300%	5min	(3)	41.10	39.0	43.2	41.1	3.9	4.3	
250%	4min	4min (2)	34.25	32.6	36.0	34.3	3.3	3.6	
200%	4min	4min (2)	27.40	26.0	28.8	27.4	2.6	2.9	
150%	4min	4min (2)	20.55	19.6	21.6	20.6	2.0	2.2	
100%	4min	4min (2)	13.70	13.0	14.4	13.7	1.3	1.4	
50%	4min	4min (2)	6.85	6.6	7.2	6.9	0.7	0.7	
0%	5min	(5)	0.00	0.0	0.0	0.0	0.0	0.0	

Notes:

- (1). The loading for quick load test shall applied in at least 2 increments.
- (2). For each load increment, the load shall be maintained for minimum period of 5min. or until equilibrium is reached whichever is greater. Equilibrium shall mean a rate of settlement not exceeding 0.25mm in one increment.
- (3). The full test load shall remain in place for a minimum period of 5min. or until final equilibrium is reach. Recording shall be recorded in 4min. interval.
- (4). The full test load shall then be unloaded in not less than 2 decrements with intervals of not less than 5min., with recovery being measured at each unloading stage. Recording shall be recorded in 4 minutes interval.
- (5). The final rebound shall be recorded in 5min after the entire load has been removed.



Myit-nge New Railway Bridge Project

Dynamic Load Test




GeoLab Myanmar Co., Ltd.


Instrumentation Report

Figure 6: Load Test Sequence and Cargo Arrangement for Static Load Cases


LOAD CASE-1



LOAD CASE-2



LOAD CASE-3



LOAD CASE-4




Figure 10: Load Case I



Figure 11: Load Case IV



VWSG Installation Photos



Figure 13: Avg: Stress Intensity of Static Loading CASE I,II,III,IV





Figure 19: Dynamic Avg Stress Intensity Changes @ Train Speed 10mph

Data-Logger Set-up



A Role of Geotechnical Engineer




- **Scope of Work:** Site Investigation and Field Testing, Laboratory Testing, Design and Construction Supervision, Verified Actual Field.
- **Duty:** Must be professional, positive thinking, innovative and technical support.
- **Responsibility:** **Testing**, **Design**, **Site Supervision** and **Project Management** (if any).
- **Skills:** Task Risk Assessment (TRA), Field Oriented, Practicing in HSE Policy.
- **Ultimate Goal:** Environmental Prevention, Public Safety and Solution Provision.

Thank you for your attention!




Pile Testing Instrumentation

- 1 Displacement Transducers | 05
- 2 Load Cells | 11
- 3 Multi-Channel Dataloggers | 18
- 4 Strain Gauges | 04
- 5 Retrievable Extensometers | 06
- 6 In-Place Inclinometers | 13
- 7 Sister Bars | 04
- 8 Telltales | 07




Concrete Dam Instrumentation

- 1 In-Place Inclometers | 13
- 2 Extensometers | 06-07
- 3 Pendulums | 14
- 4 Multi-Channel Dataloggers | 18
- 5 Piezometers | 08-09
- 6 Load Cells | 11
- 7 Tiltmeters | 14
- 8 Crackmeters | 05
- 9 Embedment Jointmeters | 05
- 10 Temperature Gauges | 22
- 11 Embedment Strain Gauges | 04
- 12 Earth Pressure Cells | 11




Earth Dam Instrumentation

- 1 Soil Strainmeters | 05
- 2 Settlement Sensors | 10
- 3 Heavy Duty Piezometers | 08
- 4 Temperature Gauges | 22
- 5 Earth Pressure Cells | 11
- 6 Piezometers | 08-09
- 7 In-Place Inclometers | 13
- 8 Inclometer Probes | 12
- 9 Readouts | 15-16
- 10 Multiplexers | 18
- 11 Multi-Channel Dataloggers | 18
- 12 Weir Monitors | 09



Deep Excavation Instrumentation

- 1** Single-Channel Dataloggers | 17
- 2** Piezometers | 08-09
- 3** In-Place Inclinerometers | 13
- 4** Load Cells | 11
- 5** Strain Gauges | 04
- 6** Extensometers | 06-07
- 7** Tiltmeters | 14
- 8** Crackmeters | 05
- 9** Multi-Channel Dataloggers | 18
- 10** Inclinerometer Probes | 12
- 11** Jackout Pressure Cells | 11
- 12** Sister Bars | 04



Tunnelling Instrumentation

- 1** Single-Channel Dataloggers | 17
- 2** Piezometers | 08-09
- 3** Extensometers | 06-07
- 4** Load Cells | 11
- 5** NATM Pressure Cells | 11
- 6** Strain Gauges | 04
- 7** Tiltmeters | 14
- 8** Crackmeters | 05
- 9** Multi-Channel Dataloggers | 18
- 10** In-Place Inclinerometers | 13
- 11** Tape Extensometers | 07
- 12** Convergence Meters | 05

